

AKSU Journal of Agriculture and Food Sciences 10(2) 32-41, 2026

© Faculty of Agriculture, Akwa Ibom State University, Nigeria

Comparative Effects of Oven and Sun Drying on the Mineral Composition and Functional Properties of Cocoyam Flour from *Colocasia esculenta* and *Xanthosoma sagittifolium*

Nnamnso G. Charlie and Enobong O. Umoh *

Department of Agricultural Engineering, Akwa Ibom State University, Ikot Akpaden,
P. M. B., 1167, Uyo, Nigeria

*Corresponding Author E-mail: enobongumoh@aksu.edu.ng; Tel: +2348035408924

Abstract

*Cocoyam is a tropical root crop that has gained increasing attention due to its nutritional value, functional applications, and potential role in food security and industrial uses. This study was carried out to comparatively evaluate the effect of different drying methods: oven drying and sun drying, on the mineral element composition and functional properties of cocoyam: *Colocasia esculenta* and *Xanthosoma sagittifolium*. Fresh cocoyam tubers from both *Colocasia esculenta* and *Xanthosoma sagittifolium* were processed into flour. The mineral content and functional properties of the flour samples were determined in triplicates (number of replicate = 3) using standard laboratory procedures. A one-way ANOVA was used to determine the effects of drying methods on the flour mineral composition and properties at a 5% probability level. Results/findings showed that both oven and sun drying methods significantly ($p < 0.05$) affected the mineral composition of both *Colocasia esculenta* and *Xanthosoma sagittifolium*, except calcium, which was not significantly ($p > 0.05$) affected by the drying methods. Functional properties of both *Colocasia esculenta* and *Xanthosoma sagittifolium* were significantly ($p < 0.05$) affected by both oven and sun drying methods. Drying method significantly altered the final profile, indicating that value addition to cocoyam must be species- and application specific. There is no single best method; rather, the choice depends on whether the priority is maximizing mineral content (favouring sun drying) or achieving high viscosity/swelling (favouring oven drying for *Colocasia esculenta*).*

Keywords: Drying methods, Functional properties, Mineral composition, Cocoyam flour, Root and tuber crop

1.0 Introduction

Cocoyam is a tropical root crop that has gained increasing attention due to its nutritional value, functional applications, and potential role in food security and industrial uses. It belongs to the family *Araceae*, and the two most widely cultivated edible species are *Colocasia esculenta* (commonly known as taro) and *Xanthosoma sagittifolium* (tannia or new cocoyam). These crops are especially important in sub-Saharan Africa, Asia, and the Pacific Islands, where they serve as a major staple food and a source of income for rural households (Oti and Akobundu, 2010). Cocoyam is highly valued for its digestibility, hypoallergenic properties, and richness in carbohydrates, dietary fibre, and essential minerals such as calcium, magnesium, phosphorus, potassium, and iron. The starch content of cocoyam is known to be fine-grained and easily digestible, making it suitable for infant foods, the elderly, and people with digestive disorders (Adejumo and Adebayo, 2012). Furthermore, the mucilage present in cocoyam contributes to its unique textural and functional characteristics, such as thickening and binding, which are desirable in food formulations (Onyeka, 2014).

According to Ogunlakin *et al.* (2012), sun-dried cocoyam flour sample has the highest values of packed bulk density and swelling capacity, while the oven-dried sample has the lowest values. Maliki *et al.* (2020) earlier reported that no significant difference exists, in terms of water absorption capacity, oil absorption capacity and swelling capacity of cocoyam flours, across the different drying methods (sun drying, oven drying and cabinet dryer).

Cocoyam is a valuable source of essential minerals necessary for human health. It contains significant amounts of potassium, calcium, magnesium, phosphorus, iron, and zinc, which play critical roles in metabolic functions, bone health, oxygen transport, and enzyme activity (Adegunwaet *al.*, 2011). Potassium, for instance, contributes to the regulation of blood pressure and nerve transmission, while magnesium and calcium are important for muscle function and skeletal strength. Among the two major species, *Xanthosoma sagittifolium* generally exhibits a slightly higher concentration of minerals, especially calcium and magnesium, making it more nutritionally advantageous in some diets (Ukom *et al.*, 2013).

The mineral composition of cocoyam further enhances its nutritional value. Cocoyam is a good source of potassium, which plays a vital role in maintaining normal blood pressure and cardiovascular health. It also contains calcium and phosphorus, which are essential for bone and teeth development, and magnesium, which is involved in energy metabolism, nerve transmission, and muscle function. Additionally, trace elements such as iron and zinc are present in measurable quantities and contribute to blood formation and immune system function (Azeez and Madukwe, 2010).

Traditional processing methods such as boiling, roasting, drying, fermentation, and pounding are known to significantly influence the physicochemical characteristics and mineral bioavailability of root and tuber crops (Ukomet *al.*, 2017). Processing, for instance, can reduce anti-nutritional factors such as oxalates and phytates in cocoyam, which are known to interfere with mineral

absorption (Ukom *et al.*, 2013). However, it may also lead to the leaching of water-soluble nutrients and thermal degradation of sensitive minerals during cooking or drying (Enwezor *et al.*, 2015). Moreover, the method of processing directly impacts the functional properties of cocoyam flours such as water absorption capacity, swelling index, bulk density, and gelatinization behaviour which determine its suitability for different food products (Okafor and Ugwu, 2015).

Food drying is a method of food preservation in which food is dried to inhibit the growth of bacteria, yeast and mould through the removal of water (Maliki *et al.*, 2020). Drying techniques (sun, oven, or freeze-drying) reduce moisture content, enhance storability, and allow for flour production. However, high drying temperatures can affect functional properties like swelling capacity and water absorption (Okoye *et al.*, 2018; Adegunwa *et al.*, 2011). According to Umoh and Iwe (2014), processing reduces the level of mineral elements in the processed false yam samples.

Several studies have suggested that the functional and nutritional qualities of tubers can be optimized by selecting appropriate processing techniques (Adegunwa *et al.*, 2011). However, there is a paucity of comprehensive comparative data on the effects of different processing methods on the functional properties and mineral composition of the two cocoyam species. This knowledge gap hinders effective value addition and optimal utilization of cocoyam as a functional food ingredient. The aim of this study was to comparatively evaluate the effects of different processing methods, namely; oven drying and sun drying, on the mineral composition and functional properties of cocoyam (*Colocasia esculenta* and *Xanthosoma sagittifolium*).

2.0 Materials and Methods

2.1 Collection of Cocoyam Tubers

Fresh cocoyam tubers from both *Colocasia esculenta* and *Xanthosoma sagittifolium* varieties were obtained from Ukam market in Mkpato Enin Local Government Area, Akwa Ibom State, Nigeria. The species identification was authenticated by the Department of Plant Science (Botany), Akwa Ibom State University.

2.2 Preparation of Cocoyam Flour Sample

This was carried out according to the method described by Umoh and Iwe (2014). The cocoyam tubers were carefully rinsed to eliminate any soil or contaminants, and were then subjected to manual peeling to remove the outer layers, and then sliced, resulting in the consumable parts prepared for subsequent handling. The peeled and sliced cocoyam tubers were processed into flour using two drying methods: oven drying and sun drying. Portions of the peeled and sliced tubers were dried in an electric oven set at 60°C for 12 hours until a constant weight was achieved. Other portions were spread in a single layer on clean trays and allowed to dry naturally under direct sunlight between 10:00am and 4:30pm daily for five (5) days, until moisture equilibrium was reached.

The dried cocoyam products from both methods were ground into fine flour using a mechanical grinder. The resulting flour from each treatment was sieved using a mesh (0.55mm) to ensure uniformity before storage in airtight containers pending analysis (Figure 2.1).




Figure 2.1: Process flowchart for cocoyam flour production (Umoh and Iwe, 2014)

2.3 Analysis of Mineral Composition

The mineral element content of the processed cocoyam flours was determined in triplicates with number of replicates = 3, using standard laboratory procedures, as described by Umoh and Iwe (2014).

Sample Digestion: The dried and ground sample was subjected to wet digestion using a mixture of concentrated nitric acid (HNO_3) and hydrochloric acid (HCl) in a digestion chamber. The mixture was heated progressively until a clear, colourless solution was obtained, indicating

complete sample dissolution. The resulting digest was filtered and diluted to a fixed volume with de-ionized water for analysis.

Mineral Quantification: The prepared digests were analyzed for their content of calcium (Ca), magnesium (Mg), phosphorus (p), potassium (K), and iron (Fe), using Buck Scientific Atomic Absorption Spectrophotometer (AAS) model 225, made in Germany. Standard curves were prepared to facilitate accurate quantification of the minerals in both *Colocasia esculenta* and *Xanthosoma sagittifolium* samples.

Determination of Functional Properties: The functional properties of the prepared cocoyam flours were determined in triplicate with number of replicates = 3, using the methods described by Onwuka (2018) as follows:

Bulk Density: Bulk density was determined by tapping a known weight of flour into a graduated cylinder until a constant volume was achieved. The bulk density was calculated as the mass of the flour divided by its occupied volume (g/mL).

Water Absorption Capacity (WAC): WAC was measured by mixing 1g of flour with a known volume of distilled water. After allowing the mixture to stand for 30 minutes, the supernatant was centrifuged, and the water retained by the flour was determined by calculating the difference in weight.

Oil Absorption Capacity (OAC): OAC was determined by mixing 1g of flour with a known volume of edible oil. After settling for 30 minutes, the excess, unabsorbed oil was decanted after centrifugation, and the absorbed oil was calculated by weight difference.

Swelling Power: Swelling power was determined by dispersing a known weight of flour in distilled water, heating the slurry at 85°C, and then cooling it. The final volume occupied by the swollen paste was measured to determine swelling power.

Viscosity: The viscosity of standard slurry of the cocoyam flour was measured using a standard rotational viscometer. Centrifugation speed of 3000 rpm for 25 minutes was adopted under controlled temperature and shear rate conditions to assess its flow behaviour.

2.4 Experimental Design/Data Analysis

The experiment was laid out as a Completely Randomized Design (CRD). The data obtained were subjected to statistical analyses using one way Analysis of Variance (ANOVA) at 5% level of significance. Mean separation was by Duncan multiple range tests, and results expressed as Mean \pm SD (standard deviation) of triplicate determination (number of replicate = 3). The data analysis was aided by the IBM SPSS Statistical software version 20.

3.0 Results and Discussion

The experimental data consisted of mineral content (calcium, potassium, magnesium, phosphorus, iron) and functional properties (water absorption capacity, oil absorption capacity, bulk density, swelling power, viscosity) for the two species of cocoyam processed by two methods (oven-dried and sun-dried), as presented in Table 3.1, 3.2 and Table 3.3, 3.4, respectively.

3.1 Effect of Drying Method on Mineral Content

The data presented in Tables 3.1 and 3.2 show that the drying technique employed had a substantial effect on mineral preservation, which in turn influences the ultimate nutritional quality of the cocoyam flour.

Table 3.1: Mineral Content (mg/100g) for *Colocasia esculenta* based on drying method

Mineral (mg/100g)	Oven-Dried	Sun-Dried
Calcium (Ca)	28.53 ±0.57 ^a	34.33±0.91 ^a
Potassium (K)	615.97 ± 4.08 ^b	691.00 ± 1.84 ^a
Magnesium (Mg)	32.87±0.25 ^b	36.57±0.61 ^a
Phosphorus (P)	87.47±0.65 ^a	81.37 ± 1.38 ^b
Iron (Fe)	1.35±0.15 ^a	1.70±0.06 ^a

Note: Values are Mean ± SD of triplicate determination. Values within the same row with the same superscripts are not significantly different (p<0.05)

Table 3.2: Mineral Content (mg/100g) for *Xanthosoma sagittifolium* based on drying method

Mineral (mg/100g)	Oven-Dried	Sun-Dried
Calcium (Ca)	23.03±0.38 ^a	28.49 ±0.57 ^a
Potassium (K)	529.13±9.10 ^b	618.10 ± 4.48 ^c
Magnesium (Mg)	24.03±0.20 ^d	32.97 ± 0.21 ^e
Phosphorus (P)	79.31±1.16 ^e	84.70±0.76 ^f
Iron (Fe)	0.977±0.125 ^f	1.45±0.132 ^f

Note: Values are Mean ± SD of triplicate determination. Values within the same row with the same superscripts are not significantly different (p<0.05).

Overall patterns for macro-minerals (potassium and magnesium) revealed that, across both varieties (*Colocasia esculenta* and *Xanthosoma sagittifolium*), sun drying preserved considerably greater amounts of potassium (K) and magnesium (Mg) compared to oven drying, with statistical significance at $p < 0.001$ in most cases. However, high amount of calcium, potassium and magnesium have been reported to reduce blood pressure (Umoh and Iwe, 2014).

This aligns closely with prior research mentioned in the literature review, such as studies by Ukom *et al.* (2017) and Enwezor *et al.* (2015), which indicate that intense heat treatments like oven drying can cause the loss of water-soluble elements such as potassium, through leaching or thermal breakdown. The gentler, lower-heat approach of sun drying proves more effective in maintaining these vital macro-minerals, recommending its use to enhance the nutritional advantages of cocoyam flour.

In line with the macro-minerals, sun drying typically resulted in markedly better preservation of calcium (Ca) and iron (Fe) in *Colocasia esculenta* (as shown in Table 3.1). For iron across both species, sun drying offered enhanced retention, probably by reducing oxidation or reactions triggered by excessive heat. However, for calcium in *Xanthosoma sagittifolium* (Table 3.2), the variation between the drying techniques was not statistically meaningful ($p > 0.05$). This might indicate that calcium within the *Xanthosoma* structure is less prone to heat-induced loss or leaching under the tested conditions, or that the variability among the three replicates was sufficient to obscure a difference, even with a mean gap of 2.46 mg/100g.

The result for phosphorus is the most notable deviation. In *Colocasia esculenta* (Table 3.1), oven drying significantly increased the measured phosphorus content ($p < 0.05$). This contradicts the general trend for other minerals. This could be explained by the concentration effect during oven drying if the overall moisture loss was more pronounced than any actual loss of phosphorus, or perhaps due to the breakdown of phytate-P complexes during heating, making the phosphorus more extractable/measurable by the subsequent digestion method. In *Xanthosoma sagittifolium* (Table 3.2), the trend reversed with sun drying showing significantly higher level of phosphorus ($p < 0.05$), highlighting a potential species-specific response to thermal processing, as alluded to by Azeez and Madukwe (2010).

Effect of Drying Method on Functional Properties

The impact of drying method on the functional properties, which determine the suitability of the flour for specific food applications, was pronounced (Tables 3.3 and 3.4).

Sun drying consistently resulted in significantly higher WAC and OAC for both *Colocasia esculenta* and *Xanthosoma sagittifolium* ($p < 0.05$). This assertion is at variance with the earlier findings reported by Ogunlakin *et al.*, (2012); Maliki *et al.*, (2020). This is crucial, as higher absorption capacities indicate superior quality for use in products like doughs, batters, and structured foods, allowing for greater moisture/fat retention and a desirable texture (Okafor and Ugwu, 2015). The less intense drying likely preserved the porous structure of the starch granules better than the more aggressive oven drying.

Table 3.3: Functional properties for *Colocasia esculenta* based on drying method

Functional Property	Oven-Dried	Sun-Dried
WAC (g/ml)	2.300±0.100 ^a	2.517 ± 0.076 ^b
OAC (g/ml)	1.400 ± 0.100 ^b	1.883 ± 0.076 ^c
Bulk density(g/ml)	0.793±0.015 ^c	0.740 ± 0.027 ^d
Swelling power (%)	10.600±0.100 ^d	6.400 ±0.100 ^e
Viscosity (mp _a /s)	169.467±0.702 ^e	164.633±0.666 ^f

Note: Values are Mean ± SD of triplicate determination. Values within the same row with the same superscripts are not significantly different (p<0.05). WAC = Water absorption capacity, OAC = Oil absorption capacity

Table 3.4: Functional properties for *Xanthosoma sagittifolium* based on drying method

Functional Property	Oven-Dried	Sun-Dried
WAC (g/ml)	1.933±0.153 ^a	2.370 ± 0.036 ^b
OAC (g/ml)	1.267±0.252 ^b	1.767 ± 0.042 ^c
Bulk Density(g/ml)	0.630 ± 0.010 ^c	0.740 ± 0.027 ^d
Swelling power (%)	9.700±0.100 ^d	6.400 ± 0.100 ^e
Viscosity (mp _a /s)	172.967±0.208 ^e	151.37 ± 3.67 ^f

Note: Values are Mean ± SD of triplicate determination. Values within the same row with the same superscripts are not significantly different (p<0.05). WAC = Water absorption capacity, OAC = Oil absorption capacity

Conversely, oven drying yielded significantly higher swelling power and viscosity for *Colocasia esculenta* (p < 0.05). This observation is at variance with the earlier findings reported by Ogunlakin *et al.* (2012), and Maliki *et al.* (2020). This is a classic indication that severe heat treatment might have caused extensive gelatinization, leading to increased hydration potential (swelling) and intermolecular forces (viscosity). However, for *Xanthosoma sagittifolium*, the trend was mixed. Oven drying yielded significantly higher swelling power, but the viscosity difference was also significant in favour of oven drying (Table 3.4). This implies that while the starch structure of *Colocasia esculenta* is more easily disrupted by heat, leading to better swelling, both species react to oven drying in a way that increases viscosity, possibly due to the formation of more stable paste structures under rapid drying/high heat (Okafor and Ugwu, 2015).

For *Colocasia esculenta* (Table 3.3), oven drying produced significantly denser flour, suggesting the heat caused greater compaction. However, for *Xanthosoma sagittifolium* (Table 3.4), sun drying resulted in significantly denser flour. This aligns with the earlier report by Ogunlakin *et al.* (2012). This stark difference between species highlights the species-specific nature of cell wall structure and compaction behaviour, directly impacting packaging and transportation costs.

Low bulk density is desirable in infant feeding, while flours with high bulk density are used as thickeners in food products (Umoh, 2020; Kadiri and Umoh, 2026).

4.0 Conclusion

Based on the results/findings obtained, the following conclusions are drawn:

The sun drying method is superior for mineral preservation in cocoyam flour, particularly for potassium, magnesium, calcium, and iron, making it the recommended technique for enhancing the nutritional profile of the processed products.

The functional properties are strongly dependent on the thermal intensity of the drying method. Sun-dried flour is better suited for applications requiring high water/oil binding (e.g., baked goods where moisture retention is key), whereas oven-dried flour (especially *Colocasia esculenta*) exhibits characteristics (higher swelling/viscosity) suitable for thickening agents in soups and porridges.

Colocasia esculenta is inherently richer in most essential minerals (Ca, K, Mg, Fe) and exhibits better water-holding and swelling characteristics than *Xanthosoma sagittifolium* across both drying methods studied.

Processing method significantly ($p < 0.05$) alters the final profile, indicating that value addition to cocoyam must be species- and application specific. There is no single best method; rather, the choice depends on whether the priority is maximizing mineral content (favouring sun drying) or achieving high viscosity/swelling (favouring oven drying for *Colocasia esculenta*).

References

- Adegunwa, M. O., Alamu, E. O., Bakare, H. A., and Adebowale, A. A. (2011). Effect of processing on the nutritional contents of yam and cocoyam tubers. *Journal of Applied Biosciences*, 46, 3086–3092.
- Adejumo, B. A., and Adebayo, H. J. (2012). Nutritional composition and antinutritional factors of wild cocoyam (*Colocasia esculenta*) from South West Nigeria. *Journal of Natural Sciences Research*, 2(6), 79–85.
- Azeez, M. A., and Madukwe, D. K. (2010). Mineral composition of *Colocasia esculenta* and *Xanthosoma sagittifolium*. *Journal of Food Science and Technology*, 47(6), 671–676.
- Enwezor, V. O., Ubah, S. C., and Oko, A. O. (2015). Effects of processing methods on the nutritional composition of cocoyam. *Nigerian Journal of Food Science and Technology*, 3(2), 45–52.
- Kadiri, M. O. and Umoh, E. O. (2026). Assessment of proximate composition and functional properties of watermelon (*Citrullus lanatus*) seed flour. *International Journal of*

Engineering and Modern Technology, 12(4), 35-46.
<https://doi.org/10.56201/ijemt.vol.12.no4.2026.pg35.46>

- Ogunlakin, G. O., Oke, M. O., Babarinde, G. O., Olatunbosun, D. G. (2012). Effect of drying methods on the proximate composition and physic-chemical properties of cocoyam flour. *American Journal of Food Technology*, 7(4), 245-250.
<https://doi.org/10.3923/ajft.2012.245.250>
- Maliki, K, Ajayi, A, Makanjuola, O. M., and Adebowale, O. J. (2020). Drying effect on the proximate composition and functional properties of cocoyam flour. *International Journal of Mathematical and Computational Sciences*, 14(12), 2020.
- Okafor, J. N., and Ugwu, F. M. (2015). Functional and pasting properties of flour from cocoyam tubers as affected by processing methods. *Nigerian Food Journal*, 33(1), 83–89.
- Onyeka, J. (2014). *Status of cocoyam (Colocasia and Xanthosoma spp.) in West and Central Africa: Production, household importance and the threat from leaf blight*. CGIAR Research Program on Roots, Tubers and Bananas (RTB). Lima: International Institute of Tropical Agriculture (IITA).
- Onwuka, G. I. (2018). *Food analysis and instrumentation (theory and practice)*. Naphthali Prints, Somolu, Lagos, Nigeria. Pp 1 – 100.
- Oti, E., and Akobundu, E. N. T. (2010). Comparative evaluation of cocoyam (*Xanthosoma sagittifolium*) and cassava (*Manihot esculenta*) as starch sources in infant foods. *African Journal of Food Science and Technology*, 1(1), 001–005.
- Ukom, A. N., Ojmelukwe, P. C., and Alamu, E. O. (2013). Effect of processing on the proximate composition, anti-nutritional factors and functional properties of cocoyam flour. *Journal of Food Processing & Technology*, 4(8), 1000261.
- Umoh, E. O. and Iwe, M. O. (2014) Effect of processing on the nutrient composition of false yam (*Ipomoea pes-caprae*) flour. *Nigerian Food Journal*, 32(2), 1-7.
[https://doi.org/10.1016/S0189-7241\(15\)30111-9](https://doi.org/10.1016/S0189-7241(15)30111-9)
- Umoh, E. O. (2020). Evaluation of proximate composition, functional properties and anti-nutritional factors of aerial yam-soybean flour. *International Journal of Food Science and Nutrition*, 5(1), 70-74.
- Umoh, E. O., Uko, I, Akpan, I. A., and Edem, S. P. (2024). Effect of different drying methods on the proximate composition and energy value of green plantain (*Musa paradisiaca*) flour. *AKSU Journal of Agriculture and Food Sciences*, 8(2), 154-162.
<https://doi.org/10.61090/aksuja.2024.026>